



Agenda topics

- 1 Previous work
- 2 Assumptions
- 3 Options considered
- 4 Shortlisted options


- 5 Current project status
- 6 Key issues
- 7 Next steps





Previous work

- Wolgan Road slope stability studies
- Report on route constraints
- Report on preferred corridor location
- Report on preferred alignment within preferred corridor






Criteria for new road options

- Eastern side of valley preferred on geotechnical grounds
- Road suitable for single unit truck and passable by semi trailer
- Preferred gradient 10% 15%, absolute maximum grade 17%
- Resilient to weather conditions, minor rockspills
- Designed to facilitate maintenance
- Preference to maintain Donkey Steps as functioning route


Initial option development




Refer following slides of initial options

































Option 6A















Option 8A










Initial Option sifting


- Option 1 cuts into rock outcrops, not desired visual outcome X
- Option 2 east side of Donkey Steps, bridges over steep terrain √
- Option 3 west side of Donkey Steps, bridges over steep terrain √
- Option 4 (scenario for minimum standard) narrow cross section and tight curvature X
- Option 5 deep cut allows lower traverse of slope and improved horizontal alignment √
- Option 6 /6A (scenario for long bridge) costly and uses existing western side X
- Option 7 flatter grade at expense of travel time and driveability X
- Option 8 /8A Donkey Steps routes, not meeting minimum standards X
- Option 9 similar to Option 2 & 3, impacts Donkey Steps X

Shortlisted options


- Option 2 east side of Donkey Steps, bridges over steep terrain √
- Option 3 west side of Donkey Steps, bridges over steep terrain √
- Option 5 deep cut allows lower traverse of slope and improved horizontal alignment √
























Current status

- Draft 95% report and drawings issued to Council for comment
- Ongoing studies are:
 - Ecology impacts fieldwork completed
 - Option costing underway

Key issues

- Delivery timeframes
- Obtaining funding for construction
- Planning approvals
- Construction procurement





Next steps

- Incorporate council feedback on draft report
- HSiD / risk workshop to come
- Complete remaining study tasks and issue final report
- Engage with NSW planning and stakeholders on required approvals
- Engage with funding authorities
- Preferred option refinement



Thank you



wsp.com